

WINDOW PROFILES



DOOR PROFILES


DOOR SCHEDULE									
DOOR NO.	SIZE	DOOR				FRAME		HARDWARE (SEE SPECS)	REMARKS
		UNITS	MATERIAL	KIND	FINISH	MATERIAL	FINISH		
101	3'-0"x 7'-0"x 1-3/4"	1	STEEL CUSTOM ENTRY DOOR	SWING	PREFINISHED	STEEL	PREF.	ENTRY KEY LOCK	HARDWARE BY OWNER - TO INCLUDE HINGE STOP
101A	3'-0"x 6'-8"x 1-3/8"	1	SOLID CORE 4 PANEL	SWING	STAINED	WOOD	VARN.	PASSAGE KNOB SET	HARDWARE BY OWNER - EXISTING ANTIQUE WOOD PANELS TO BE USED
102	7'-0"x 7'-0"x 1-3/4"	1	SOLID FRAME & PANEL	SWING	STAINED	WOOD	VARN.	BARN LATCH HARDWARE	CUSTOM DOOR & HARDWARE BY OWNER
103	3'-0"x 7'-0"x 1-3/4"	1	SOLID CORE ENTRY DOOR	SWING	PREFINISHED	WOOD	PAINT	ENTRY KEY LOCK	HARDWARE BY OWNER - TO INCLUDE HINGE STOP
103A	2'-6"x 6'-8"x 1"	1	FROSTED GLASS SHOWER DOOR	SWING	PREFINISHED	GLASS	PREF.	EXG. HRDWRE.	BY OWNER - TEMPERED
103B	3'-0"x 6'-8"x 1-3/8"	1	HOLLOW CORE 6 PANEL-BIFOLD	SWING	PREFINISHED	WOOD	PAINT	PASSAGE KNOB SET	PANTRY DOOR - PROVIDE CAT DOOR
104	2'-6"x 6'-8"x 1-3/8"	1	HOLLOW CORE 6 PANEL	POCKET	PREFINISHED	WOOD	PAINT	PRIVACY LOCKSET	BATHROOM DOOR
201A, 201B, 204A	4'-0"x 6'-8"x 1-3/8"	3	LOUVERED BIFOLDS	SWING	PREFINISHED	WOOD	PAINT	PASSAGE KNOB SET	CLOSET, LAUNDRY DOORS
201C	2'-6"x 6'-8"x 1-3/8"	1	LOUVERED BIFOLDS	SWING	PREFINISHED	WOOD	PAINT	PASSAGE KNOB SET	CLOSET, LAUNDRY DOORS
202	2'-6"x 6'-8"x 1-3/8"	1	HOLLOW CORE 6 PANEL	SWING	PREFINISHED	WOOD	PAINT	PRIVACY LOCKSET	BATHROOM DOOR
203	3'-0"x 6'-8"x 1-3/4"	1	SOLID CORE ENTRY DOOR	SWING	PREFINISHED	WOOD	PAINT	ENTRY KEY LOCK	HARDWARE BY OWNER - TO INCLUDE HINGE STOP - HALF GLAZED
203A, 203B	4'-0"x 6'-8"x 1-3/8"	2	LOUVERED BIFOLDS	SWING	PREFINISHED	WOOD	PAINT	PASSAGE KNOB SET	CLOSET, LAUNDRY DOORS
203, 204B	3'-0"x 6'-8"x 1-3/8"	2	HOLLOW CORE 6 PANEL	SWING	PREFINISHED	WOOD	PAINT	PRIVACY LOCKSET	BEDROOM, STUDIO DOORS

WINDOW SCHEDULE									
NO.	DESCRIPTION	WINDOW				SIZE	NO. UNITS		REMARKS
		TYPE	GLAZE	KIND	FINISH				
B1	HORIZONTAL SLIDER	VINYL	DOUBLE	SLIDER	PREFIN	5'-0" X 5'-0"	2		EXCEEDS 5.7 S.F. FIRE EGRESS
W2	DOUBLE HUNG VINYL CLAD	VINYL	DOUBLE	DOUBLE HUNG	PREFIN	2'-4" X 5'-2"	2		PELLA 350 SERIES

ROOM FINISH SCHEDULE													
ROOM NO.	ROOM	FLOOR FINISH	BASE TRIM		WALLS		CEILING		MOLDINGS			PAINT	
			MATER.	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	BASE	CROWN	CHAIR	COLOR	DESCR.
101	FOYER	QUARRY TILE	TILE	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	4"	6"	3"		SEMI GLOSS
102	LIVING ROOM	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	6"	6"	3"		SATIN
103	KITCHEN	OAK FLOORING/ CERAMIC TILE	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	6"	6"	3"		SEMI GLOSS
104	BATH	CERAMIC TILE	TILE	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	4"	3"	-		SATIN
105	PANTRY	CERAMIC TILE	TILE	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	4"	-	-		SATIN
201	OFFICE	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	6"	-	3"		SATIN
202	BATH	CERAMIC TILE	TILE	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	4"	3"	-		SEMI GLOSS
203	BEDROOM	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	6"	6"	3"		SATIN
204	HALL	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	6"	6"	3"		SATIN
205	LAUNDRY	CERAMIC TILE	TILE	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	4"	-	-		SEMI GLOSS
STR	STAIRWELL	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	ORANGE PEEL	6"	6"	-		SATIN
CLO	CLOSET	OAK FLOORING	WOOD	PAINT	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	6"	-	-		SATIN
FURN	FURNACE	VCT	VINYL	PREF.	DRYWALL	ORANGE PEEL	DRYWALL	KNOCK DOWN	4"	-	-		SEMI GLOSS
MS	MOP SINK	CERAMIC TILE	-	-	-	-	-	-	-	-	-		
PAT	PATIO	PATIO PAVERS	-	-	-	-	-	-	-	-	-		
BAL	BALCONY	STEEL	-	-	-	-	-	-	-	-	-		

ALL PAINT CHOICES BY OWNER

- NOTES
- CABINET FINISH TO BE RESPONSIBILITY OF OWNER.
 - PRIME ALL SURFACES PRIOR TO APPLYING FINAL PAINT FINISH.
 - ALL SURFACES RECEIVE A FINISH UNLESS NOTED OTHERWISE.
 - EXPOSED CONCRETE FLOOR TO RECEIVE 2 COATS OF SEALER.
 - PAINT ALL GRILLS, VENTS, PIPING & ETC. TO MATCH ADJACENT FINISH.
 - PROVIDE CORNER GUARDS ON ALL EXTERIOR CORNERS.
 - ALL EXPOSED MECHANICAL EQUIPMENT TO BE PRIMED AND PAINTED WITH #5205 GRAY METAL PRIMER IF NOT PREFINISHED.
 - DOOR FRAMES & TRIM SHALL BE PAINTED WITH SEMIGLOSS ENAMEL



REVISIONS	BY

SENIUK RESIDENCE

528 TITAN STREET
PHILADELPHIA, PA 19147

PHOTODESIGN.NET
732 RANDOM STREET
PHILADELPHIA, PA
19106
215-629-0295

AGE QUOD AGIS

ARCHITECTURAL STAMP

DRAWN
SRH
CHECKED

DATE
7/29/2015
SCALE
AS INDICATED
JOB NO.
15-014
SHEET

A-701

OF X SHEETS